KOLAR DIVISION.

Dated 11th July 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 26th July 1913, for constructing quarters for two head constables at Stevens Camp, Kolar Gold Fields. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (100) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing quarters for two head constables at Stevens Camp, Kolar Gold Fields," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	*Per*	*Quantity*
Earthwork excavating foundation and filling basement ...	C. yd.	20
Burnt stone in mud	C. ft.	811
Burnt brick in mud	,,	908
Burnt brick in chunam	,,	205
Burnt stone slabs, dressed, with cutting grooves to pillars ...	S. ft.	172
Teakwood battened door with iron clamps, painting, etc. ...	,,	66
Do windows, ventilators, etc., do ...	,,	41
Teakwood work with wood oiling	C. ft.	38
Roofing with 1st class Mangalore tiles with teak re epers 2"×1" and chunam borders, reepers to be oiled	Sqr.	6·55
Mangalore ridge tiles set in mortar	R. ft.	19
Mangalore ventilating tiles	No.	8
Teakwood ornamental eave boards with painting	R. ft.	76
Teakwood finials, small, at end of eaves	No.	8
Plastering with chunam	Sqr.	25·11
Pointing with chunam	,,	1·97
Coping with brick in chunam and plastering	R. ft.	63
V.-shaped concrete drains with cement plastering	,,	34
White and colourwashing	Sqr.	25·11
Flooring with 3" concrete and plastering with chunam ...	,,	3·62
Forming roads	L. S.	
Flooring with gravel	C. yd.	4
Clearing site and levelling ground	L. S.	

NOTE.—The above quantities represent quarters for only one head constable and they should be multiplied by two as quarters for two head constables have to be constructed.

Dated 11th July 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 26th July 1913, for constructing quarters for two head constables at Robertsonpet, Kolar Gold Fields. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A. M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for head constables at Robertsonpet," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	*Per*	*Quantity*
Earthwork excavating foundation and filling basement ...	C. yd.	20
Burnt stone in mud	C. ft.	811
Burnt brick in mud	„	908
Burnt brick in chunam	„	205
Burnt stone slabs, dressed, with cutting grooves to pillars ...	S. ft.	172
Teakwood battened door with iron clamps painting, etc. ...	„	66
Do windows, ventilators, etc., do ...	„	41
Teakwood work with wood oiling	C. ft.	38
Roofing with 1st class Mangalore tiles with teak reepers 2″×1″ and chunam borders, reapers to be oiled	Sqr.	6·55
Mangalore ridge tiles set in mortar	R. ft.	19
Mangalore ventilating tiles	No.	8
Teakwood ornamental eave boards with painting	R. ft.	76
Teakwood finials, small, at end of eaves...	No.	8
Plastering with chunam	Sqr.	25·11
Pointing with chunam	„	1·97
Coping with brick in chunam and plastering	R. ft.	63
V-Shaped concrete drains with cement plastering	„	34
White and colourwashing	Sqr.	25·11
Flooring with 3″ concrete and plastering with chunam ...	„	3·62
Forming roads	L. S.	
Flooring with gravel	C. yd.	4
Clearing site and levelling ground	L. S.	

NOTE.—The above quantities represent quarters for only one head constable and they should be multiplied by two as quarters for two head constables have to be constructed.

V. AIYASWAMI IYER,
Executive Engineer.